BANGALORE DIVISION.

Dated 10th November 1909.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 4th December 1909, for restoring the Nallurhalli tank, Registered No. 171, Bangalore Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1910.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 120, one hundred and twenty, only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Nallurhalli tank, Registered No. 171, Bangalore Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract estimate of restoring Nallurhalli tank, Registered No. 171 of Bangalore Taluk:—

Items of work.	*Per*	*Quantity.*
Bund R. L. 55·00—		
Earthwork	C. yds.	10,500
Gravel backing to revetment with one mile lead	„	473
Old stone work	„	540
Turfing	S. yds.	3,444
Grades stones	Each	25
Index stones	...	25
B. M. stones	...	2
Registered No. stone	...	1
Gauge stone	...	1
New stone work	C. yds.	1,451
Sluice No. I—		
Cutting, opening and refilling bund	„	90
Dismantling and removing old sluice	L. S.	
Concrete in surki	C. ft.	262
Burnt brick in surki	„	810
Burnt stone slabs	S. ft.	344
Boring holes and dressing gibbet stone	L. S.	
Providing sluice plug with iron rod and chain, etc.	„	
Plastering with surki	Sqr.	7·69
Dismantling and re-building revetment	C. yds.	30
Ring bund	L. S.	
Sluice No. II—		
Add for sluice No. 2 as above	...	...
Waste-weir 147′ long (left)—		
Earthwork	C. yds.	470
Stone in chunam	C. ft.	2,037
Brick in do	„	45
Rough stone work	C. yd.	254
Stone slabs	S. ft.	479
Plastering with chunam	Sqr.	·68
Pointing with do	„	22·86

K. KRISHNA IYENGAR,
Executive Engineer.